

NASA/TM-1998-206561



Linear Aerospike SR-71 Experiment (LASRE): Aerospace Propulsion Hazard Mitigation Systems

*Masashi Mizukami, Griffin P. Corpening,
Ronald J. Ray, Neal Hass, and Kimberly A. Ennix
Dryden Flight Research Center
Edwards, California*

*Scott M. Lazaroff
NASA Johnson Space Center
Houston, Texas*

National Aeronautics and
Space Administration

Dryden Flight Research Center
Edwards, California 93523-0273

July 1998

NOTICE

Use of trade names or names of manufacturers in this document does not constitute an official endorsement of such products or manufacturers, either expressed or implied, by the National Aeronautics and Space Administration.

Available from the following:

NASA Center for AeroSpace Information (CASI)
7121 Standard Drive
Hanover, MD 21076-1320
(301) 621-0390

National Technical Information Service (NTIS)
5285 Port Royal Road
Springfield, VA 22161-2171
(703) 487-4650

LINEAR AEROSPIKE SR-71 EXPERIMENT (LASRE): AEROSPACE PROPULSION HAZARD MITIGATION SYSTEMS

Masashi Mizukami,^{*} Griffin P. Corpening,[†] Ronald J. Ray,[†] Neal Hass,[†] Kimberly A. Ennix[†]

NASA Dryden Flight Research Center

Edwards, California

Scott M. Lazaroff[†]

NASA Johnson Space Center

Houston, Texas

Abstract

A major hazard posed by the propulsion system of hypersonic and space vehicles is the possibility of fire or explosion in the vehicle environment. The hazard is mitigated by minimizing or detecting, in the vehicle environment, the three ingredients essential to producing fire: fuel, oxidizer, and an ignition source. The Linear Aerospike SR-71 Experiment (LASRE) consisted of a linear aerospike rocket engine integrated into one-half of an X-33-like lifting body shape, carried on top of an SR-71 aircraft. Gaseous hydrogen and liquid oxygen were used as propellants. Although LASRE is a one-of-a-kind experimental system, it must be rated for piloted flight, so this test presented a unique challenge. To help meet safety requirements, the following propulsion hazard mitigation systems were incorporated into the experiment: pod inert purge, oxygen sensors, a hydrogen leak detection algorithm, hydrogen sensors, fire detection and pod temperature thermocouples, water misting, and control room displays. These systems are described, and their development discussed. Analyses, ground test, and flight test results are presented, as are findings and lessons learned.

Nomenclature

canoe aerodynamically-shaped pod, housing
 fluid and other systems in LASRE

GH₂ gaseous hydrogen

H₂ hydrogen

H ₂ O	water
He	helium
LASRE	Linear Aerospike SR-71 Experiment
LN ₂	liquid nitrogen
LO ₂	liquid oxygen
model	top portion of LASRE, shaped like one-half of a lifting body
N ₂	nitrogen
O ₂	oxygen
P	hydrogen tank pressure, psi
P _{amb}	ambient pressure, psia
P _{calib}	pressure during calibration, psia
psi	pounds per square inch
psia	pounds per square inch, absolute
psig	pounds per square inch, gage
P _{SL}	sea level pressure, psia
R	gas constant
T	hydrogen gas temperature, R
TEA-TEB	triethylaluminum-triethylborane
V	hydrogen tank volume, in ³
Z	compressibility
Δm _{H₂}	change in mass of hydrogen in tanks, lbm
%H ₂	volume fraction of hydrogen
%H ₂ _{meas}	volume fraction of hydrogen, measured
%O ₂	volume fraction of oxygen
%O ₂ _{meas}	volume fraction of oxygen, measured

^{*} Aerospace Engineer, AIAA Member.

[†] Aerospace Engineer.

Copyright © 1998 by the American Institute of Aeronautics and Astronautics, Inc. No copyright is asserted in the United States under Title 17, U.S. Code. The U.S. Government has a royalty-free license to exercise all rights under the copyright claimed herein for Governmental purposes. All other rights are reserved by the copyright owner.

Introduction

For hypersonic and space vehicles that are reusable or piloted, safety is an exceptionally important consideration. For piloted vehicles, this consideration is a result of the possible tragic consequences of a mishap. For reusable launch vehicles, cost is the major driver; the total operational costs must be minimized, including the high cost of losing an expensive vehicle and its payload as a result of a mishap. For a flight research project, safe flight can be considered as important as the technology being investigated.

A major hazard posed by the propulsion system of hypersonic and space vehicles is the possibility of a fire or explosion in the vehicle environment. These systems store a large amount of potential energy in the form of fuel, oxidizer, high pressures or a combination of these.^{1,2} The three ingredients essential to the production of fire are fuel, oxidizer, and an ignition source (except in the case of hypergolics and pyrophorics, which can combust without an ignition source). Minimizing or detecting those three ingredients in the vehicle environment mitigates the hazard. In addition to sound design and operational practices, it is often necessary to provide dedicated hazard mitigation systems.

The Linear Aerospike SR-71 Experiment (LASRE) is a flight experiment of a reusable launch vehicle

propulsion concept done in cooperation with the industry. NASA Dryden Flight Research Center, Edwards, California was responsible for the flight test.³ The experiment consisted of a linear aerospike rocket engine integrated into one-half of an X-33-like lifting body shape, carried on top of an SR-71 aircraft (figs. 1, 2). Unlike conventional bell nozzle rockets, the linear aerospike engine can compensate for ambient back-pressure effects to provide higher performance over a wide range of altitudes. However, external flow slipstream effects on the nozzle flow may reduce performance. Therefore, the primary objective of LASRE was to evaluate flight effects on aerospike engine performance at several altitudes and Mach numbers. Although LASRE is a one-of-a-kind experimental system, it had to be rated for piloted flight, which demands a high degree of safety. A rapid prototyping approach was taken to hardware development. This approach resulted in an extended series of tests to troubleshoot and validate the integrated system. These tests included various functional tests such as 'cold flows' of inert fluids, 'ignition tests' using LO_2 and triethylaluminum-triethylborane (TEA-TEB), and actual 'hot fires' of the engine.

A simplified schematic of fluid systems in the LASRE pod is shown in figure 3. Essentially, this was a flying rocket engine test facility. The model is the top portion shaped like half of a lifting body. The canoe is an





Figure 1. LASRE configuration mounted on SR-71 aircraft.



EC 97-44295-108

Figure 2. SR-71 and LASRE in flight.




Figure 3. Simplified schematic of LASRE fluid systems.

aerodynamically-shaped pod, housing several fluid (and other) systems. A 4000 psi gaseous hydrogen (H_2) blowdown system, containing about 20 lb of H_2 , provided fuel to the engine. A liquid oxygen (LO_2) system, containing about 330 lb of LO_2 , and pressurized to about 365 psi, provided the oxidizer. Both H_2 and LO_2 could be dumped overboard through the engine. H_2 could also be expelled overboard through dump lines, and LO_2 pressure could be released through a vent line. Triethylaluminum-triethylborane (TEA-TEB), a pyrophoric, was used to initiate combustion in the engine. Engine coolant water, pressurized to 800 psi, flowed through channels drilled

in the engine block and out the water exit line. Two 9000 psi gaseous helium (He) systems provided LO_2 pressurant, water pressurant, line purges, TEA-TEB cartridge expulsion and pneumatic valve actuation. The SR-71 contained water for pod misting, and liquid nitrogen (LN_2) for pod inert purge.

Even before hazard mitigation systems were incorporated, the soundness of the underlying propulsion system itself had to be assured. The system was intended to be fail-safe for single-point failures. Component burst and proof factors were equal to or greater than those used in typical missile and space

systems.⁴ The H_2 and LO_2 systems were leak checked as much as was feasible on the integrated pod, using long-term pressure decay, bubble fluid, an ultrasonic leak detector, a thermal conductivity leak detector, an electrochemical hydrogen sensor, and blowdown testing.

Flammability limits for $H_2 - O_2 - N_2$ mixtures at sea level are about 4 percent H_2 and 4 percent O_2 , and are fairly independent of each other (fig. 4). The limits remained about the same throughout the LASRE flight envelope, extending up to an altitude of 50,000 ft, and were not significantly narrowed by reduced pressures at those altitudes.⁵ Calculation of combustion conditions at equilibrium or for detonation showed that even for low flammable concentrations of H_2 and O_2 , temperatures and pressures high enough for catastrophic consequences could develop. Therefore, a ground rule was established that O_2 and H_2 concentrations in the pod should be maintained below 4 percent during the entire mission, because any combustion in the pod was considered unacceptable.

To help meet safety requirements, propulsion hazard mitigation systems were incorporated in LASRE. These systems were: a pod inert purge, O_2 sensors, a H_2 leak detection algorithm, H_2 sensors, fire detection and pod temperature thermocouples, water misting, and control room displays. These systems are described, and their development discussed. Analyses, ground test, and flight

test results are presented, as are findings and lessons learned. Use of trade names or names of manufacturers in this document does not constitute an official endorsement of such products or manufacturers, either expressed or implied, by the National Aeronautics and Space Administration.

Propulsion Hazard Mitigation Systems

The following sections discuss the systems and methods used to mitigate propulsion hazards. Findings and lessons learned as a result of tests performed are also presented.

Pod Inert Purge

The pod cavity was purged with inert N_2 gas, for several reasons. The primary purpose was to minimize the presence of oxidizer in the pod environment to below 4 percent O_2 by displacing air out of the pod. The purge may also reduce the presence of fuel by displacing any leaked H_2 . The H_2 and LO_2 valves and some of the electronics boxes were purged with N_2 , to minimize ignition sources. This purge surrounded the electronics with inert gas, and prevented moisture caused by water misting from coming into contact with the electronics.

Figure 5 shows a schematic of the N_2 purge system. N_2 was supplied from two LN_2 Dewar flasks onboard




Figure 4. Flammability limits of $H_2 - O_2 - N_2$ mixtures at sea level.

the SR-71. LN_2 was vaporized by electric heaters, it was dispersed into the pod through perforated piccolo tubes near the front of the pod, and also into the electronics boxes and valves. The two Dewar flasks held a total of 100 liters (180 lb) of LN_2 . The flow rate was about 2.5 lb/min, or 34 standard cubic feet per minute, for an operating duration of 72 minutes. These flow rates gave about 0.3 volume change-outs per minute on the ground, and 2.4 change-outs per minute at an altitude of 50,000 ft. For ground operations, N_2 was directly provided from a ground cart to conserve the onboard LN_2 supply. During flight, flow could be turned on or off from the SR-71 rear cockpit, and the operating pressure was monitored in the control room to verify flow.

Purge effectiveness was evaluated primarily by using O_2 sensors distributed in the pod. Preliminary ground testing revealed that it took a long time to establish a purged environment, and the pod panels had to be well-sealed to maintain it. Therefore, a separate *monster purge* was implemented to establish an initially purged environment by using ground service equipment that fed large quantities of N_2 directly into the pod. During subsequent ground tests an adequate purge was confirmed. In flight however, substantial infiltration of external air occurred shortly after takeoff and purge effectiveness was quickly lost, with O_2 levels reaching nearly 21 percent. Therefore, attempts were made to seal gaps in the pod by using elastic materials such as foam rubber and caulking. Also, the second LN_2 Dewar flask was added, and purge flow rate was doubled to current levels (2.5 lb/min). In addition, a valve was placed in the purge vent line, which could be remotely actuated from the cockpit. With the valve open, the purge gas flowed through the pod and out the vent as originally designed, which also allowed any major leaks to be vented out of the pod. With the valve closed, the purge gas maintained a positive pressure in the pod, thus reducing air infiltration. The purge gas flowed out from any remaining leak paths. A subsequent flight test demonstrated adequate purge performance for flight, up to about Mach 0.9 and an altitude of 26,000 ft, with O_2 levels below 4 percent. Figure 6 shows Mach number, altitude, and the measured O_2 levels during a portion of the flight. The canoe O_2 sensor that reads consistently low O_2 levels is located close to a purge piccolo tube near the front of the canoe. The spike above 4 percent is believed to be telemetry noise. A preliminary assessment of additional data suggested that purge integrity may be maintained up to Mach 1.6 and an altitude of 50,000 ft. It was observed that with the vent valve closed, pressure was maintained in the pod during climb and descent. During climb, ambient pressure

decreased, and pod pressure was maintained above ambient pressure, which aided purge effectiveness. However, during descent the opposite effect occurred, which made it difficult to maintain an adequate purge. These tests demonstrated that it is important to provide an adequate purge flow rate, and to seal the vehicle well against outside air infiltration.

Oxygen Sensors


Twelve oxygen sensors were located in the pod to detect the presence of oxidizer, eight in the canoe and four in the model. The purpose of these sensors was to determine inert purge effectiveness, infiltration of outside air, and the presence of any leaked LO_2 . Commercially available electrolytic sensors were used, originally intended for automotive applications. Each sensor was installed in a temperature-controlled canister which was heated to about 115 °F, to reduce effects of ambient temperature changes on the readings. These sensors were point measurements that would not detect air or oxygen which could have been trapped in other areas, but the number and distribution of the sensors were judged sufficient to characterize overall O_2 levels in the pod.

It was evident from data at altitude that these sensors actually measured the partial pressure of O_2 , but volume fraction is of greater interest than partial pressure for determining the flammability of mixtures. Therefore, volume fraction of O_2 ($\%O_2$) was calculated by correcting the measured partial pressure of O_2 ($\%O_{2_{meas}}$) to sea level pressure (P_{SL}), using ambient pressure (P_{amb}), as follows:

$$\%O_2 = \%O_{2_{meas}} \frac{P_{SL}}{P_{amb}} \quad (1)$$

Accuracy of the sensor at sea level, according to the specification sheet, was 1 percent. But for a given volume fraction of O_2 , as altitude increased, ambient pressure decreased, and the partial pressure of O_2 decreased, approaching sensor accuracy limits. As a result, at high altitudes O_2 volume fraction determined from sensor readings appeared erratic.

A test program was undertaken to better characterize sensor accuracy at altitude. In a small test chamber, sensors were exposed to a range of O_2 concentrations varying from 0 percent to 21 percent, at a range of pressure altitudes from sea level to 80,000 ft. Because sensors have a life of about 2 years, new sensors as well as older ones were tested to help determine aging



980349

Figure 6. Nitrogen purge effectiveness in flight, from takeoff up to Mach 0.9 and an altitude of 26,000 ft.

effects. Representative results for 0 percent, 1 percent, 2 percent and 5 percent O_2 concentrations are shown in figure 7(a). Accuracy at sea level appears much better than the specified 1 percent accuracy, but a distinct drop-off is seen above an altitude of 30,000 ft. To compensate for the drop-off, a fifth-order polynomial correction was applied to the average of the sensor readings (fig. 7(b)). Ninety-nine percent confidence intervals for the corrected readings, based on the t-distribution, were less than 1.3 percent up to an altitude of 50,000 ft (fig. 7(c)).

Rules were established for interpreting and acting on O_2 sensor data during flight. If any O_2 sensor, plus its uncertainty, exceeded a specified threshold level (nominally 4 percent), steps would be taken to secure the system and mitigate the hazard, typically by dumping the H_2 overboard.

Clearly, it was important to validate O_2 sensor accuracy before use, especially because these sensors were being used outside their originally intended environment. Characteristics of other types of sensors, or sensors from other manufacturers, might be entirely different.


Hydrogen Pressure Decay Leak Detection

In order to infer the presence of fuel in the pod, a real-time pressure-decay method was used to detect leaking hydrogen. Conventionally, pressure-decay leak detection takes a long time to perform, and is done during system checkout. A noticeable pressure drop in the gaseous hydrogen tanks during flight operation would indicate a large leak, or perhaps a thermal transient. However, as a result of the unavailability of hydrogen sensors, a pressure-decay method was implemented for real time in-flight use. It was for detection of leaks from the H_2 tanks in a static mode only, and not for detection of leaks in the H_2 lines or during flow.

In theory, the hydrogen tank leak rate can be determined from the change in mass of hydrogen in the tanks (Δm_{H_2}) as follows:


$$\Delta m_{H_2} = \frac{V}{R} \left(\frac{P}{ZT} - \frac{P_0}{Z_0 T_0} \right) \quad (2)$$

Tank pressure (P) was measured by a pressure transducer. Hydrogen gas temperature (T) was measured by two redundant thermocouples mounted on probes




(a) Pressure altitude compared with percent O_2 , for 5 percent, 2 percent, 1 percent and 0 percent O_2 mixtures.

Figure 7. Oxygen sensor altitude chamber test data.



(b) Pressure altitude compared with percent O_2 with fifth order correction, for 5 percent, 2 percent, 1 percent and 0 percent O_2 mixtures.



(c) Pressure altitude compared with 99 percent confidence intervals for 5 percent, 2 percent and 1 percent O_2 mixtures.

Figure 7. Concluded.

inside the tanks, which were averaged together. Note, that to obtain an accurate measurement of gas temperature under changing conditions, a tank surface measurement would have been inadequate. Tank volume (V) was assumed to be constant. Compressibility (Z) was a function of P and T , and the subscript 0 denotes initial conditions. R is the gas constant for H_2 .

In software, digital low-pass filtering was applied to the Δm_{H_2} signal, to remove high frequency random noise, and to facilitate data interpretation. The filter time constant was adjustable, and was set by the user to obtain a readable signal, while preserving reasonable response time and quick recovery from data spikes. Magnitude limits were imposed to prevent telemetry data spikes from corrupting the calculation. The calculation could be configured for either hydrogen or inert helium as the working gas. The resulting Δm_{H_2} signal was displayed on a scrolling time history display (fig. 8).

The ability to detect leaks depended on discerning small changes in pressure and temperature, which was a function of instrumentation accuracy. The trace showed good stability under the varying ambient conditions of flight. Uncertainty analysis indicated that a mass loss of 0.15 lb or more could be detected. Ground testing, done by releasing controlled small amounts of gas from the tanks and observing the trace, showed that mass loss as low as 0.03 lb could be detected.

In the control room, if a mass loss rate of greater than 0.03 lb was seen in 8 minutes or less, it would be considered a positive determination of leakage, and steps would be initiated to secure the system by dumping propellants overboard. This leak rate corresponds to about 4 percent of the N_2 purge flow rate in the vicinity of the H_2 tanks, or about 1460 standard cubic inches per minute. This amount was judged to be

the minimum leak rate reliably detectable in a reasonable timeframe. However, this is still a substantial and potentially hazardous quantity of hydrogen that is capable of locally forming combustible mixtures in the pod. Lower leak rates could possibly be detected over a longer period of time.

The H_2 leak detection algorithm was a useful tool and was the only available means of H_2 leak detection on LASRE, but could not be relied upon to detect all hazardous leaks. This algorithm could detect moderate to large tank leaks, or smaller leaks over a long period of time. However, it could not detect small but still hazardous leaks in a timely manner, nor did it detect leaks in the H_2 lines.

Hydrogen Sensors

Although H_2 sensors were not used, they would have constituted a more direct way to detect the presence of fuel. Sensors were planned to be strategically positioned within the canoe and model. The sensor proposed for use was based upon a design developed by Sandia National Laboratories, Albuquerque, New Mexico.⁶ The sensor element was a Palladium-Nickel patch that has a current passing through it. When present, hydrogen freely infiltrates the lattice network of the crystal, causing a change to the electrical resistance of the element proportional to the local concentration. The element was temperature regulated by a controller, which aided in the response time of the sensor and removed one of the operational variables. The advertised range of detection was 1 percent to 100 percent volume fraction, with 0.5 percent accuracy.

The suitability and accuracy of the sensor in a flight environment needed to be ascertained. A test chamber was used to simulate pressure altitudes. Testing was conducted with pure N_2 and with calibration gases of specific concentrations of H_2 in N_2 , at discrete ambient




Figure 8. Hydrogen tank leak detection algorithm scrolling time history plot display.

pressure points ranging from 2 psia to 13.5 psia. The sensor heating element mitigated temperature effects.


Preliminary data for seven sensors with a 3 percent H_2 concentration by volume are shown in figure 9(a). It is clear from the data that when the ambient pressure was reduced the sensor measured concentration was also lowered and a linear relationship existed between ambient pressures and the measured concentration. Therefore, the H_2 sensors appear to measure partial pressure of the gas to be detected, much like the O_2 sensors. If this phenomenon was not accounted for, and the sensor readings ($\%H_{2_{meas}}$) were used without correction during flight, the readings could potentially lead to the false conclusion that the flammability limits had not yet been reached. Like the O_2 sensors, the following correction algorithm could be applied real-time during flight using ambient pressure measurements (P_{amb}) in the pod and the pressure at which the sensors were calibrated (P_{calib}), to obtain percent volume of hydrogen ($\%H_2$) present.

$$\%H_2 = \%H_{2_{meas}} \frac{P_{calib}}{P_{amb}} \quad (3)$$

Results of applying this simple correction to the raw data are shown in figure 9(b). Stable readings were seen up to nearly 27,000 ft pressure altitude. Deviation from 3 percent actual concentration indicates a bias error, but it was believed this could be corrected with a more rigorous calibration program. Above an altitude of 27,000 ft, the accuracy limitation of the sensor is reflected in the nonlinear deviation and data scatter. Very similar results were achieved using a 10 percent H_2 concentration.


Unfortunately, once installed in the pod, the system could not be made to function correctly, apparently because of design flaws in the H_2 sensor controller. Programmatic and schedule constraints ruled out the possibility of troubleshooting to correct the system, so the H_2 sensors were not installed for flight.

Certainly, a H_2 detection system would be highly desirable for hazard mitigation. Bench test results were promising for future flight applications. However, H_2 sensors and systems that are qualified for use in inert background, with varying pressures and temperatures and that are robust and compact enough for flight application are difficult to find.^{7,8} H_2 detection technologies can be pursued for future projects, as this type of fuel becomes more prevalent.



(a) Pressure altitude compared with percent H_2 measured, for 3 percent H_2 mixture.

Figure 9. Hydrogen sensor altitude chamber test data.



(b) Pressure altitude compared with percent H_2 , for 3 percent H_2 mixture.

Figure 9. concluded.

Fire Detection and Pod Temperature Thermocouples

Fifteen thermocouples were distributed throughout the pod for sensing heat from nearby combustion. Thermocouples are commonly used for local fire detection. Procedurally, if high temperatures that were far above expected ambient total temperatures were seen (especially locally), fire would be indicated and steps would be taken to dump the propellants and secure the aircraft.

The thermocouples were also used to monitor pod environment temperatures, because certain components were temperature limited, such as the composite H_2 tanks and electronics. Flight data (fig. 10) showed that, except for some areas near cryogenic components, the pod thermal environment was quite benign throughout the mission profile. During ground operations and in flight up to Mach 1.6 and an altitude of 50,000 ft, temperatures typically ranged from 45 °F to 85 °F. This benign environment was unexpected, given the wide range of external static and total temperatures throughout the mission. If pod temperatures had approached the H_2 tank temperature limit of 130 °F, steps would have been taken to cool the pod by decelerating the aircraft or turning on the water mist. If these measures had not been successful, the H_2 tanks

would have been depressurized by dumping the contents overboard.

Water Misting and Coolant System

The coolant water system was used to provide a cooling water mist for the pod, and to recirculate coolant for the electronics. The recirculating coolant was required anytime the pod was powered up. The mist was to be turned on only when necessary and appropriate for pod cooling, such as during high stagnation temperature flight conditions

Figure 11 shows a schematic of the system. About 20 gallons of water was carried aboard the SR-71. The recirculating coolant flow rate was 3 gallons per minute (gpm), and the mist flow rate was 0.18 gpm. The water was chilled by cold air from the SR-71 environmental control system. It was important to verify that the N_2 purge was on before turning on the water mist, to prevent moisture from entering the electronics boxes. Figure 12 shows the altitude and temperature regimes where the water mist boils into vapor; condensing water was undesirable, because it could cause hardware problems. The upper temperature limit for the composite high-pressure tanks is also indicated. Clearly, the usable range for water mist is limited if




Figure 10. Pod in-flight thermal environment, up to Mach 1.6 and an altitude 50,000 ft.




Figure 11. Pod water-misting and coolant system schematic.




Figure 12. Pod water-misting envelope, pod temperature compared with pressure altitude.

condensation is to be avoided. Also, water mist was not for use as a fire suppressant, and could aggravate electrical fires.


The original dual coolant pumps experienced repeated failures, because they were not designed for continuous service. These pumps were replaced with a more robust single pump. In practice, the water mist system was never used in flight because additional cooling was not necessary and because there were concerns about hardware damage from water condensation.

Control Room Displays

Propulsion systems and fire hazard mitigation system parameters were monitored in real time using control room displays. Two displays (not shown) were dedicated to monitoring propulsion system parameters and general system health. These displays schematically

represented the propellant feed systems, and were used for decision making during tests and missions. Additional displays and strip charts showed more detailed and time history data of specific parts of the propulsion and fire hazard mitigation systems.

One display was primarily used for monitoring of the fire hazard mitigation systems and parameters (fig. 13). This display included: a time history plot of the H_2 leak detection algorithm; bar charts and digital values of the fire detection thermocouples and O_2 sensors; and digital indicators of LN_2 purge and water misting and coolant systems. The operator of this display could easily switch to time histories of the fire detection, thermocouples, O_2 sensors, or H_2 sensors by selecting the appropriate on-screen button. A keyboard interface allowed real-time setup and resets of the leak detection algorithm. All critical parameters changed from green,



980359

Figure 13. Primary control room display for fire hazard mitigation systems.

to yellow, then red, as they approached and then exceeded predetermined limits.

Ground tests and inert flight tests helped validate and mature the control room displays and operating procedures. Control room displays, although they may appear overly detailed, proved indispensable during the extended development and troubleshooting program, and for determining system status and performance.

Conclusions

The LASRE experiment incorporated a number of propulsion hazard mitigation systems. Hazards were mitigated by minimizing or detecting the three ingredients essential to the production of fire: fuel, oxidizer, and ignition source. The major findings were as follows.

For inert purge of the vehicle cavity, it was important to provide an adequate purge flow rate and to seal the vehicle well against outside air infiltration. Those efforts reduced the in-flight cavity O_2 levels from nearly 21 percent to below 4 percent.

Oxygen and hydrogen sensor accuracies in flight needed to be considered. Accuracy in terms of volume fraction-of-gas degraded at high altitudes. This was because the sensors actually measured partial pressure of the gas. For a given volume fraction-of-gas, as altitude increased, ambient pressure decreased, and the partial pressure of the gas also decreased, approaching sensor accuracy limits. Sensor accuracy could be better characterized by calibration at reduced pressures. Oxygen sensors were a mature technology and were value-added for safety monitoring. Accurate and robust hydrogen sensors able to operate in an inert flight environment were identified as an important safety technology, requiring further development.

A pressure- and temperature-based gaseous propellant tank leak-detection algorithm was found to be a useful tool, but could not be relied upon to detect all hazardous leaks. This algorithm could detect moderate to large tank leaks, or smaller leaks over a long period of time. However it could not detect small, but still hazardous, leaks in a timely manner, nor did it detect leaks in the H_2 lines or during flow.

The pod thermal environment was found to be surprisingly benign throughout the mission, up to

Mach 1.6 and an altitude of 50,000 ft, given the wide range of static and total temperatures. The water mist system was never used in flight, because additional cooling was not necessary, and because of concerns about hardware damage from water condensation.

Detailed control room displays proved indispensable during the extended development and troubleshooting program, and for determining system status and performance.

References

¹"Safety Standard for Hydrogen and Hydrogen Systems," NASA NSS-1740.16, Office of Safety and Mission Assurance, Washington DC, 1995.

²"Safety Standard for Oxygen and Oxygen Systems," NASA NSS-1740.15, Office of Safety and Mission Assurance, Washington DC, 1996.

³Corda, Stephen, David P. Lux, Edward T. Schneider, and Robert R. Meyer Jr., "Blackbird Puts LASRE to the Test," *Aerospace America*, vol. 36, no. 2, pp. 24-29, Feb. 1998.

⁴"Standard General Requirements for Safe Design and Operation of Pressurized Missile and Space Systems," MIL-STD-1522A (USAF), May 1984.

⁵Benz, F. J. and P. L. Boucher, "Flammability Characteristics of Hydrogen/Oxygen/Nitrogen Mixtures at Reduced Pressures," in: *Proceedings of the Workshop on the Impact of Hydrogen on Water Reactor Safety*, vol. 3, M. Berman, ed., SAND-81-0661, vol. 3, 1981.

⁶Miller, S. L., K. L. Hughes, J. L. Rodriguez, and P. J. McWhorter, "Calibration and Characterization of Wide Range Hydrogen Sensors," in: *Advanced Earth-to-Orbit Propulsion Technology Conference*, CP-3282, vol. 1, Huntsville, AL, 1994.

⁷Hunter, Gary W., *A Survey and Analysis of Commercially Available Hydrogen Sensors*, NASA TM-105878, 1992.

⁸Hunter, Gary W., *A Survey and Analysis of Experimental Hydrogen Sensors*, NASA TM-106300, 1992.

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE July 1998		3. REPORT TYPE AND DATES COVERED Technical Memorandum
4. TITLE AND SUBTITLE Linear Aerospike SR-71 Experiment (LASRE): Aerospace Propulsion Hazard Mitigation Systems			5. FUNDING NUMBERS WU 242-33-02-00-33-00-T15	
6. AUTHOR(S) Masashi Mizukami, Griffin P. Corpening, Ronald J. Ray, Neal Hass, Kimberly A. Ennix, and Scott M. Lazaroff				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) NASA Dryden Flight Research Center P.O. Box 273 Edwards, California 93523-0273			8. PERFORMING ORGANIZATION REPORT NUMBER H-2268	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) National Aeronautics and Space Administration Washington, DC 20546-0001			10. SPONSORING/MONITORING AGENCY REPORT NUMBER NASA/TM-1998-206561	
11. SUPPLEMENTARY NOTES Presented at the 34th AIAA/ASME/SAE/ASEE Joint Propulsion Conference, Cleveland, Ohio, July 13-15, 1998. Masashi Mizukami, Griffin P. Corpening, Ronald J. Ray, Neal Hass and Kimberly A. Ennix, NASA Dryden Flight Research Center, Edwards, California; Scott M. Lazaroff, NASA Johnson Space Center, Houston, Texas.				
12a. DISTRIBUTION/AVAILABILITY STATEMENT Unclassified—Unlimited Subject Category 20			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) A major hazard posed by the propulsion system of hypersonic and space vehicles is the possibility of fire or explosion in the vehicle environment. The hazard is mitigated by minimizing or detecting, in the vehicle environment, the three ingredients essential to producing fire: fuel, oxidizer, and an ignition source. The Linear Aerospike SR-71 Experiment (LASRE) consisted of a linear aerospike rocket engine integrated into one-half of an X-33-like lifting body shape, carried on top of an SR-71 aircraft. Gaseous hydrogen and liquid oxygen were used as propellants. Although LASRE is a one-of-a-kind experimental system, it must be rated for piloted flight, so this test presented a unique challenge. To help meet safety requirements, the following propulsion hazard mitigation systems were incorporated into the experiment: pod inert purge, oxygen sensors, a hydrogen leak detection algorithm, hydrogen sensors, fire detection and pod temperature thermocouples, water misting, and control room displays. These systems are described, and their development discussed. Analyses, ground test, and flight test results are presented, as are findings and lessons learned.				
14. SUBJECT TERMS Fire prevention, Flight safety, Hypersonic vehicles, Reusable launch vehicles, Rocket engines			15. NUMBER OF PAGES 22	
			16. PRICE CODE A03	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT Unlimited	